



SCOPE OF WORK

STANDARDS AND DESCRIPTION OF WORK PERFORMANCE

Interior Final Cleaning

The Contractor's **Terms and Conditions** are by reference a part of all **Scope of Work** requirements.

Construction Requirements:

Generally speaking the work of Trade Contractors and their employees is expected to be performed in a good and workmanlike manner. Workmanlike quality is defined as workmanship that meets or exceeds those criteria indicated in applicable building codes, using materials and installation methods identified in the construction plans and this Scope of Work.

Code Requirements:

All jobs shall conform to those standards stipulated in the building code, mechanical code, plumbing code, and electrical code applicable in the local jurisdiction. All construction on Contractor's jobsites shall meet or exceed NAHB Performance and Building Standards.

General Comments:

Contractor considers our Trade Contractors to be experts at producing a high-quality job. Everyone on our construction team / staff, Trade Contractors, and suppliers—however, must recognize the importance of providing quality in both the product and service areas while on our jobsites and in the homes of our purchasers.

Since we work as a team, poor quality or service, from any of us, reflects unfavorably on all of us. An exceptional level of product quality and highly effective service can help us all to expand our business.

Contractor's definition of quality construction also requires that every job be completed correctly the first time. When this does not occur, it costs all of us additional time and money, destabilizes trust with the homebuilder and hurts our reputations as quality builders. That is why, in situations where construction was not completed in a quality

manner, prompt corrective action is required to remedy specific deficiencies.

In the following information the term Site Superintendent shall refer to any Contractor representative with authority to perform the specified task. The term Trade Contractor shall mean the Trade Contractor's organization or any representative that is assigned the authority to perform the specified task.



Interior Prep and Final Cleaning

Overview:

4way-drywall-carpet prep. - Final

Entire house needs to be cleaned and ready for occupancy.

Procedure: 4-Way

1. Sweep and vacuum all wall cavities
2. Garage swept
3. Basement Vacuumed
4. Clean debris from all window wells
5. Exterior walk the site and pick up trash and construction debris and place in dumpster
6. Vacuum and wipe down top of fireplace
7. Vacuum behind fireplace cavities
8. Vacuum behind flu chases
9. Vacuum tubs

Procedure: Drywall Cleaning

1. Vacuum against all walls
2. Vacuum all floors
3. Vacuum out electrical boxes
4. Vacuum out window tracks and window sills
5. Sweep basement floors
6. Sweep and scrape glue off floors preparing for hard floor surfaces



Procedure: Final Clean/Carpet prep

This Clean is not just prep for carpet it is also the final clean. Even though carpet and paint touch up has not been completed yet the house needs to be completely cleaned. After carpet and paint touch up has been completed a Touch Up Final clean will take place.

- 1 . Prepare floors for carpet
 - A) Scrape any glue or uneven surface preparing for carpet install
 - B) Sweep and vacuum all floors to remove dust, debris so floor are ready for carpet to be installed.
 - C) Remove all tape and paper from hardwood and tile floors
- 2 . All cabinets, drawers, and closets need to be vacuumed out, and wiped down with a damp cloth.
- 3 . Tops and bottoms of cabinets wiped down
- 4 . All carpets need to be vacuumed.
- 5 . All tape residue needs to be cleaned off hardwood and tile floors around the baseboards
- 6 . All tile/wood floors need to be wiped down so that they are dirt, dust, grout, paint and **streak free**.
- 7 . All walls, trim, sills and fixtures (lights and plumbing) must be dusted and cleaned. Be careful that you do not wipe down the walls with too wet of a rag; it may remove the paint & cause paint problems.
- 8 . All appliances need to be sticker free, and wiped down inside and out and ready for use. All warranty booklets and information needs to be placed in the cabinet drawer closest to the oven.
- 9 . Clean all floors behind and underneath appliances. (stove, washer, dryer and refrigerator)
- 10 . Vacuum all carpet edges and baseboards with a bristled hose end. Don't use a hard plastic nozzle as it leaves marks on the baseboards. It may be necessary to clean junctions of base and case and inside corners with Q-tips to remove dust.
- 11 . All tubs, showers, sinks and toilets must be cleaned and ready for use. All fixtures need to appear as new. Please notify Project Manager if any scratches or cracks are found in any tubs, showers or toilets.
- 12 . Exterior door thresholds need to be cleaned and all stickers and protective coverings removed.
- 13 . All plant and niche shelves must be wiped down clean.
- 14 . Window tracks need to be cleaned, lift out window to clean tracks.
- 15 . Vacuum out all heat registers and cold air returns
- 16 .

- 17. All mechanical rooms must be cleaned and furnaces, water heaters, softener units and all other mechanical and plumbing units wiped down clean.
- 18. Mechanical room floor vacuumed
- 19. All unfinished basements must be vacuumed clean.
- 20. All cold storage rooms must be vacuumed clean and 2x4's removed and stacked neatly in cold storage
- 21. **A sign must be left on each exterior door explaining that the house has been cleaned and that no shoes or cutting are allowing in house. If found violating this request may result in a \$100 fine by builder.**
- 22. Make a detailed list of any items that may need additional work, such as caulking or any other item noticed that would not meet Contractor's Construction quality assurance checklists. This list should be faxed into the office and not left on site.
- 23. Paint cans need to be stacked in basement
- 24. Power wash garage and all exterior concrete
- 25. Spray off garage door

Procedure: Touch up Final Clean

- 1: Vacuum carpet
- 2: Vacuum off tops of baseboards
- 3: Final mop on all hard surface floors
- 4: Touch up bathroom faucets and sinks
- 5: Double check everything on the house and make sure it is clean and dust free

Cleaning steps:

4-Way Clean
 Post Drywall Clean
 Final Clean/Carpet prep
 Touch up Final Clean



4-Way Cleaning

Trade Contractor _____

Job Name/No. _____

PO No. _____

___ Sweep and vacuum all wall cavities

___ Garage swept

___ Basement Vacuumed

___ Clean debris from all window wells

___ Exterior walk the site and pick up trash and construction debris and place in dumpster

___ Vacuum and wipe down top of fireplace

___ Vacuum behind fireplace cavities

___ Vacuum inside flue chases

___ Vacuum out tubs

___ Vacuum under and behind tubs

Signature _____ Date _____

Project Manager

Signature _____ Date _____

Trade Contractors



Post Sheetrock clean

Trade Contractor _____

Job Name/No. _____

Po No. _____

- ___ Vacuum against all walls
- ___ Vacuum all floors
- ___ Vacuum out electrical boxes
- ___ Vacuum out window tracks and window sills
- ___ Sweep basement floors (unfinished basement)
- ___ Vacuum off steps and vacuum out gap on sides of steps
- ___ Sweep and scrape glue off floors preparing for hard floor surfaces
- ___ Vacuum out garage
- ___ Scrape off any glue on garage floor

Signature _____ Date _____
Project Manager

Signature _____ Date _____
Trade Contractors



Interior Final Cleaning

Trade Contractor _____

Job Name/No. _____

PO No. _____

- ___ All cabinets, drawers, and closets need to be vacuumed out, and wiped down with a damp cloth.
- ___ All carpets need to be vacuumed and spot cleaned.
- ___ All tile/wood floors need to be wiped down so that they are dirt, dust, paint and streak free.
- ___ Tape residue removed off all hardwood and tile floors
- ___ All **walls**, trim, sills and fixtures (lights and plumbing) must be dusted and cleaned. Be careful that you do not wipe down the walls with too wet of a rag; it may remove the paint & cause paint problems.
- ___ All appliances need to be sticker free, and wiped down inside and out and ready for use. All warranty booklets and information needs to be placed in the cabinet drawer closest to the oven.
- ___ Clean all floors behind and underneath appliances. (stove, washer, dryer and refrigerator)
- ___ Vacuum all carpet edges and baseboards with a bristled hose end. Don't use a hard plastic nozzle as it leaves marks on the baseboards. It may be necessary to clean junctions of base and case and inside corners with Q-tips to remove dust.
- ___ All tubs, showers, sinks and toilets must be cleaned and ready for use. All fixtures need to appear as new. Please notify Project Manager if any scratches or cracks are found in any tubs, showers or toilets.
- ___ Exterior door thresholds need to be cleaned and all stickers and protective coverings removed.
- ___ All plant and niche shelves must be wiped down clean.
- ___ All mechanical rooms must be clean and furnaces, water heaters, softener units and all other mechanical and plumbing units wiped down clean.
- ___ All unfinished basements must be vacuumed clean
- ___ All cold storage rooms must be vacuumed clean.
- ___ All heat registers and cold air returns vacuumed out
- ___ A sign must be left on each exterior door explaining that the house has been cleaned and that no shoes or cutting are allowing in house. If found violating this request may result in a \$100 fine by builder.
- ___ Make a detailed list of any items that may need additional work, such as caulking or any other item noticed that would not meet Contractor's Construction quality assurance checklists. This list should be faxed into the office and not left on site.

- ☐ Exterior and garage concrete power washed
- ☐ Spray off garage door
- ☐ Paint cans stacked in basement

Signature _____ Date _____
Project Manager

Signature _____ Date _____
Trade Contractors



Touch up Final Clean

Trade Contractor _____

Job Name/No. _____

PO No. _____

- ___ Vacuum carpet
- ___ Vacuum off tops of baseboards
- ___ Final mop on all hard surface floors
- ___ Touch up bathroom faucets and sinks
- ___ Double check everything on the house and make sure it is clean and dust free

Signature _____ Date _____
Project Manager

Signature _____ Date _____
Trade Contractors